

INSTALLATION INSTRUCTIONS

- A- REMOVE (6) MOUNTING SCREWS (1) HOLDING SHOWER PANEL (2) TO FRAME (3). CAREFULLY REMOVE SHOWER PANEL (2); DISCONNECT AIR LINE (4) AND WATER LINE (5) FROM AIR CONTROL VALVE.
- B- BLOCK OUT EXISTING WALL FOR MOUNTING FRAME (3) 19" x 9" x 4-3/8" DEEP.
- C- INSTALL MOUNTING FRAME WITH SUITABLE FASTENERS; DRILL THRU HOUSING TO WALL AND INSTALL WALL ANCHORS. FASTENERS BY OTHERS. ROUGH-IN SUPPLIES; MOUNTING FRAME MAY BE POSITIONED FOR SUPPLIES THROUGH TOP OR FROM BOTTOM.
- H- AFTER THOROUGHLY FLUSHING THE SUPPLY LINES, MAKE-UP SUPPLY CONNECTIONS (1/2" NPS FEMALE).

- (NOTE: SUPPLY INLET CONNECTION WILL ACCOMODATE 1/2" NPT MALE ADAPTER). THREAD FLEX CONNECTOR HOSE (6) TO VALVE INLET AND TO SUPPLY STUBOUTS.
- D- RECONNECT AIR LINE (4) AND WATER LINE (5). TIGHTEN FERRULE NUTS HANDTIGHT.
- E- REATTACH (6) MOUNTING SCREWS (1).



NOTE:
MAXIMUM RECOMMENDED WORKING PRESSURE IS 100 PSI; TEMPERATURE IS 130F; OUTLET TEMPERATURE IS RECOMMENDED AT A MAXIMUM OF 105F.

WARNING:
PRIOR TO MAKING INSTALLATION, SUPPLY LINES MUST BE FLUSHED OF ALL FOREIGN MATERIAL SUCH AS PIPE DOPE, CHIPS, ETC. VALVE MUST BE DRAINED PRIOR TO BEING SUBJECTED TO FREEZING TEMPERATURES. MAXIMUM RECOMMENDED OUTLET WATER TEMPERATURE IS 105F.

<p>ACORN ENGINEERING COMPANY P.O. BOX 3527 INDUSTRY, CA. 91744 (626) 336-4561 FAX (626) 961-2200</p>	TITLE		
	<p>PENAL-PAK FRONT ACCESS WALL SHWR. - 1741-3-FA/1741-4-FA - NEW STYLE</p>		
	MANUFACTURE DATE	DATE ISSUED	DRAWING NUMBER
<p>SEPTEMBER 2001</p> <p>TO PRESENT</p>	<p>11/08/01</p> <hr/> <p>DATE REVISED</p> <p>05/24/10</p>	<p>9925-120-004</p>	



REFERENCE DRAWING	
SHOWERHEAD	9970-000-003
TINNERMAN NUTS	9951-007-001
PANEL SCREWS	9951-005-001
T/P VALVE ADJ	9900-007-001
T/P VALVE	9975-005-002



INSTALLATION INSTRUCTIONS:

- A. REMOVE (6) MOUNTING SCREWS (1) HOLDING SHOWER PANEL (2) TO FRAME (3). CAREFULLY REMOVE SHOWER PANEL (2).
- B. BLOCKOUT EXISTING WALL FOR MOUNTING FRAME (3) 24" H x 9" W x 4-3/8" DEEP.
- C. INSTALL MOUNTING FRAME WITH SUITABLE FASTENERS; DRILL THRU HOUSING TO WALL AND INSTALL WALL ANCHORS. FASTENERS BY OTHERS. ROUGH-IN SUPPLIES; MOUNTING FRAME MAY BE POSITIONED FOR SUPPLIES THROUGH TOP OR FROM BOTTOM.
- D. AFTER THOROUGHLY FLUSHING THE SUPPLY LINES, MAKE-UP 1/2" NPS TOP SUPPLY CONNECTIONS (4). HOSE END CONNECTIONS WILL ACCOMMODATE 1/2" NPT MALE ADAPTER. (APPLIES FOR -8 AND -8MV)

- E. ASSEMBLE SHOWER PANEL TO THE MOUNTING FRAME USING HARDWARE (1) PROVIDED.

NOTE

MAXIMUM RECOMMENDED WORKING PRESSURE IS 100 psi; MAX TEMPERATURE IS 130°F; OUTLET TEMPERATURE RECOMMENDED IS 110°F MAXIMUM.

WARNING

PRIOR TO PERFORMING INSTALLATION, SUPPLY LINES MUST BE FLUSHED OF ALL FOREIGN MATERIALS SUCH AS PIPE DOPE, METAL CHIPS, ETC.

VALVE MUST BE DRAINED PRIOR TO BEING SUBJECTED TO FREEZING TEMPERATURES.

<p>ACORN ENGINEERING COMPANY P.O. BOX 3527 Industry, CA 91744 15125 Proctor Ave Industry, CA 91746 (626) 336-4561 FAX (626) 961-2200</p>	<p>TITLE PENAL-PAK FRONT ACCESS SHOWER 1741FA-8/8MV</p>		
	<p>MANUFACTURE DATE</p> <p>APRIL 2024</p> <p>TO PRESENT</p>	<p>DATE ISSUED</p> <p>03/05/2024</p> <p>DATE REVISED</p> <p>12/18/25 B</p>	<p>DRAWING NUMBER</p> <p>9925-121-001</p>